



3 x 75kW

Tritium Charge Points For Osprey Charging

Case Study

Wakefield



Linbrooke

People • Technology • Connectivity



Rapid EV Charger Installation.



Client: Osprey Charging Network

DNO: Northernpowergrid.com



**The College Pub
Wakefield, UK**



Design, installation & testing of 3 Tritium Charge Points & LV distribution board to BS7671.



Electrical infrastructure for one 240kVA three phase supply to supply 3 Tritium chargepoints, including all offsite civils and reinstatement, installation of 145m of 3c 300mm mains cable and associated jointing and termination into a 400A heavy duty cut out.



All onsite and off site civils including feeder pillar base, 3 x car charging base, bollard installation, signage installation and all trenching from feeder pillar to charge points.



Civils
All on site & off site



2
Installed In Two
Weeks From
Design Approval

3
EV Chargers
Installed



Linbrooke
People • Technology • Connectivity



0844 800 0983



info@linbrooke.co.uk | www.linbrooke.co.uk



“Linbrooke provide a smooth process from start to finish, frequently going above and beyond to help us deliver sites efficiently and to a high standard. They are particularly proactive with resolving on-site issues.”

Lydia Macdonell
Project Manager
Osprey Charging Network



Linbrooke

People • Technology • Connectivity



0844 800 0983

Unit 2-4 Sheffield Business Park,
Churchill Way, Chapeltown
Sheffield, S35 2PY,

www.linbrooke.co.uk



Scan The QR code
To Connect With
Linbrooke.