



3 x 75kW

Tritium Charge Points For Osprey Charging Case Study

Barnsley



Linbrooke

People • Technology • Connectivity



Rapid Charge Points Installation.



Client: Osprey Charging Network
DNO: Northern Powergrid
iDNO: ESPE



Wombwell Lane
Retail Park
S70 3NS



75kW
Chargers

3
EV Chargers
Installed

Civils
On site & Off site



Project Overview:



Design, installation & testing of 3 Tritium Charge Points & LV distribution board to BS7671.



Electrical infrastructure for one 195kVA three phase supply to supply 3 Tritium chargepoints, including all off site civils and reinstatement, installation of 40m of 3c 300mm mains cable and associated jointing and termination into a 400A heavy duty cut out.



All onsite and off site civils including feeder pillar base, 3 x car charging base, bollard installation, signage installation and all trenching from feeder pillar to charge points.





“Linbrooke provide a smooth process from start to finish, frequently going above and beyond to help us deliver sites efficiently and to a high standard. They are particularly proactive with resolving on-site issues.”

Lydia Macdonell
Project Manager
Osprey Charging Network



Linbrooke

People • Technology • Connectivity



0844 800 0983

Unit 3-4 Sheffield Business Park,
Churchill Way, Chapeltown
Sheffield, S35 2PY,

www.linbrooke.co.uk



Scan The QR code
To Connect With
Linbrooke.